



NOTES:

1. This detail illustrates a method of eliminating pitch pockets and a satisfactory method of grouping piping that must come up above the roof surface.
2. This hood detail depicts jobsite fabricated construction. Manufacturers such as Portals Plus offer pre-fabricated boots and other materials which will serve this purpose. One typical configuration is shown in the inset. Specifics on these proprietary designs vary greatly, and individual manufactures specifications should be consulted for their use.

TITLE	
PIPING THROUGH ROOF DECK	
NAME	
ERS-MB-18	
APPROVED BY	DATE
APPLICABLE TO MODIFIED	
SYSTEMS	
ECOLOGY ROOF SYSTEMS	1400 HARBOR BLVD. SUITE #601 FULLERTON, CA 92835